



DOOR SCHEDULE **FINISH SCHEDULE**

DOOR SCHEDULE											FINISH SCHEDULE														
NUMBER	OPENING SIZE (WxH)	TYPE	DOOR			FRAME			HARDWARE GROUP	FIRE RATING	NOTES	#	ROOM NAME	FLOOR	BASE	WSCT	WALLS				CEILING	CABINETS			NOTES
			MATL	THRESH	FINISH	TYPE	MATL	FINISH									NORTH	EAST	SOUTH	WEST		HEIGHT	FACE	TOPS	
1	3'-0" x 7'-0"	2	ALUM/GR.	ALUM.	ANCD.	3	ALUM.	ANCD.	1	—	C	101	RETAIL SALES	SV-1	B-1/B-2	4'-0" HIGH C-1 W. EAST WALL	P-1	P-1/C-1	P-1	P-1	ACT-1	3'-0"	TRIM 3/4" PL-1	TRIM 3/4" PL-1	TRIM C-1 WAINSCOT W/PRE FINISHED METAL, PROVIDE ROUNDED EDGES.
2	3'-0" x 7'-0"	2	ALUM/GR.	ALUM.	ANCD.	3(SH)	ALUM.	ANCD.	1	—	C	102	SOUNDLOCK	C-1	B-1	—	C-1	C-1	C-1	C-1	SVRBD P-1	—	—	—	SEE DETAIL:
3	3'-0" x 7'-0"	1	WD.	ALUM.	—	1	—	—	3	—	A,B	103	FIRING LANES	SV-1	B-1	4'-0" HIGH C-1 W. WEST WALL	C-1	—	C-1	C-1	ACT-2	—	—	—	PROVIDE C-1 FINISH ABOVE BOTTOM OF 12" WIDE SILL.
4	3'-0" x 7'-0"	1	MTL.	ALUM.	—	4	—	—	3	—	A,B	104	20' x 20' YARD LANES	CONC.	B-2	—	P-2	—	P-2	—	ACT-2	—	—	—	—
5	3'-0" x 7'-0"	1	MTL.	ALUM.	—	4	—	—	3	—	A,B	105	BULLET TRAP	CONC.	B-2	—	P-2	—	P-2	—	ACT-2	—	—	—	—
6	3'-0" x 7'-0"	1	MTL.	ALUM.	—	4	—	—	3	—	A,B	106	BULLET TRAP	CONC.	B-2	—	P-2	—	P-2	—	ACT-2	—	—	—	—
7	3'-0" x 7'-0"	1	WD.	ALUM.	—	4	—	—	3	—	A,B	107	CORRIDOR	CONC.	B-2	—	P-2	P-2	P-2	P-2	ACT-2	—	—	—	—
8	4'-0" x 7'-0"	1	MTL.	ALUM.	—	4	—	—	1	—	D, 4 HD. HINGES	108	SOUNDLOCK	VCT-1	B-1	—	P-1	P-1	P-1	P-1	SVRBD P-1	—	—	—	—
9	3'-0" x 7'-0"	1	WD.	—	—	1	—	—	3	—	UNDERCUT DOOR 1"	109	MACHINE SHOP	CONC.	B-2	—	P-1	P-1	P-1	P-1	OPEN	—	—	—	—
10	3'-0" x 7'-0"	1	WD.	—	—	1	—	—	3	—	UNDERCUT DOOR 1"	110	WELDING	CONC.	B-2	—	PLYND, P-1	PLYND, P-1	PLYND, P-1	PLYND, P-1	OPEN	—	—	—	—
11	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	3	20 MIN.	—	111	PARTS ROOM	CONC.	B-2	—	P-1	P-1	P-1	P-1	OPEN	—	—	—	—
12	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	3	20 MIN.	—	112	LOUNGE	VCT-1	B-2	—	P-1	P-1	P-1	P-1	ACT-1	3'-0"/7'-0"	PL-1	PL-2	—
13	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	4	20 MIN.	—	113	CORRIDOR	VCT-1	B-2	—	P-1	P-1	P-1	P-1	ACT-1	—	—	—	—
14	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	4	20 MIN.	—	114	LAB	VCT-1	B-2	—	P-1	P-1	P-1	P-1	ACT-1	3'-0"/7'-0"	PL-1	PL-2	—
15	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	2	20 MIN.	—	115	INSTRUMENT ROOM	VCT-1	B-2	—	P-1	P-1	P-1	P-1	ACT-1	3'-0"/7'-0"	PL-1	PL-2	—
16	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	2	20 MIN.	—	116	SHOWER	VCT-1	B-2	—	P-1	P-1	P-1	P-1	SVRBD P-1	—	—	—	SEE DETAIL:
17	3'-0" x 7'-0"	1	MTL (B)	—	—	(B)	—	—	1	—	VERIFY EXIST.	117	CORRIDOR	VCT-1	B-2	—	P-1	P-1	P-1	P-1	ACT-1	—	—	—	—
18	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	2	20 MIN.	—	118	STORAGE	VCT-1	B-2	—	P-1	P-1	P-1	PLYND, P-1	ACT-1	—	—	—	—
19	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	2	20 MIN.	—	119	OFFICE	C-2	B-2	—	P-1	P-1	P-1	P-1	ACT-1	—	—	—	—
20	3'-0" x 7'-0"	1	MTL.	ALUM.	—	4	—	—	3	—	A,B, BULLETPROOF	120	STORAGE	VCT-1	B-2	—	P-1	P-1	P-1	P-1	ACT-1	—	—	—	—
21	3'-0" x 7'-0"	1	WD.	ALUM.	—	2	—	—	3	20 MIN.	A,B	121	CLASSROOM	VCT-1	B-2	—	P-1	P-1	P-1	P-1	ACT-1	—	—	—	—
22	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	2	20 MIN.	—	122	SOUNDLOCK	C-1	B-2	—	C-1	C-1	C-1	C-1	SVRBD P-1	—	—	—	—
23	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	2	20 MIN.	—	123	OFFICE	C-2	B-2	—	P-1	P-1	P-1	P-1	ACT-1	—	—	—	—
24	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	3	20 MIN.	—	124	WOMEN	EX. ST.	EX. ST.	—	P-1	P-1	P-1	P-1	PH. EX. ST.	—	—	—	PAINT ONLY NON TILED EXIST'G WALLS
25	3'-0" x 7'-0"	2	ALUM/GR.	—	—	1	—	—	2	20 MIN.	PROVIDE SIGNATURE PEN ON VEST.	125	MEN	VCT-1	B-2	4'-0" HIGH MANTLE	P-1	P-1	P-1	P-1	SVRBD P-1	—	—	—	PROVIDE MTL TRIM-PROFINISHED AT TOP OF MANTLE, SEAL ALL JOINTS
26	3'-0" (E)	1	WD.	—	—	(E)	—	—	4	—	VERIFY EXIST.	126	CORRIDOR	VCT-1	B-2	—	P-1	P-1	P-1	—	ACT-1	—	—	—	—
27	3'-0" x 7'-0"	1	WD.	—	—	1	—	—	4	—	VERIFY EXIST.	127	JAL. TOR	VCT-1	B-2	—	P-1	P-1	P-1	P-1	SVRBD P-1	—	—	—	ALUM. PAINTED
28	3'-0" x 7'-0"	2	ALUM/GR.	ALUM.	ALUM.	3	—	—	1	—	—	128	—	—	—	—	—	—	—	—	—	—	—	—	PROVIDE 3/4" SPACED 3/4" PLYND SHELVES W/ MTL BRACES TO PER PLAN
29	3'-0" x 7'-0"	1	WD.	—	—	2	—	—	2	—	—	129	—	—	—	—	—	—	—	—	—	—	—	—	—
30	2'-0" x 7'-0"	1	WD.	—	—	1	—	—	2	20 MIN.	—	130	—	—	—	—	—	—	—	—	—	—	—	—	—
31	3'-0" x 5'-4"	5B/B 12/B	WD.	—	—	—	—	—	—	—	SEE NOTE →	—	—	—	—	—	—	—	—	—	—	—	—	—	—

Notes

A. DOORS 3, 4, 5, 6, 7, 20, AND 21 TO HAVE DOUBLE GASKETED DOOR FRAMES AND SILLS, AND AUTO CLOSERS

B. DOOR FRAMES & DR# 3, 4, 5, 6, 7, 20 AND 21 TO BE SOLID GASKETED OR CONCRETE OR CMU WALLS AND PACKED SOLID WITH THE MATCHING BATTIS & FRAMED WALLS.

C. SIGN ABOVE DOOR: LETTERS CONTRASTING COLOR, THIS SIGN TO REMAIN UNLOCKED DURING BUSINESS HOURS.

D. EXTERIOR DOORS HAVE NON REMOVABLE TYPE HINGE COMPONENTS.

* THE DOOR # 20 FRAME TO BE FLUSH WITH RANGE SIDE OF CMU WALL, PROVIDE 4" FROM DOOR IN FULLY OPEN POSITION TO FACE OF DOOR # 21 IN CLOSED POSITION.

Notes

1. WALLS & SOUNDLOCK ROOMS 102, 103 AND 122 TO HAVE MIN. 1/2" ACC. BATT'S AND NO WALL PENETRATIONS.

2. CEILING & RAIS 102, 103, AND 122 TO HAVE MIN. 6" ACC. BATT'S AND NO PENETRATIONS; HEIGHT: 8'-0"

3. ALL FRAMED WALLS HAVE 5/8" TYPE 'X' GYPSUM (W.R. & NET WALLS AND GLOS.) WITH LIGHT ORANGE PEBBLE FINISH, W.O.C.

REVISIONS	BY
1	GB
2	GB
3	GB
4	GB
5	GB
6	GB
7	GB

ARCHITECT
GARY R. BAKER
 4405 W. 15TH AVE. SUITE 100
 SAN DIEGO, CA 92116
 (619) 591-1111

ACCURACY GUN
 SCHEDULES: Room/Door & DETAILS
 7818 Wilkerson Ct. San Diego, CA 92123

DESIGN DEVELOP	1	5-16-94
PLAN CHECK	2	4-17-94
BIDDING		
CONSTRUCTION		
RECORD		

DATE: 5-16-94
 SCALE: —
 DRAWN: GB
 JOB: 0325.1
 SHEET: 7
 OF 23 SHEETS